

## FLEXAMAT 10NW UV-T - NON-VEGETATED SLOPE ARMORING INSTALLATION DETAIL CONSTRUCTION NOTES:

- A MANUFACTURERS REPRESENTATIVE SHALL BE ONSITE FOR THE START OF THE INSTALLATION.
- 2. ALL SUBGRADE SURFACES PREPARED FOR PLACEMENT OF MATS SHALL BE SMOOTH AND FREE OF ALL ROCKS, STICKS, ROOTS, AND OTHER PROTRUSIONS, OR DEBRIS, OF ANY KIND.
- 3. INSTALL FLEXAMAT 10NW UV-T ROLLS THAT ARE 16' WIDE WITH AN 8" GEOGRID EXTENSION AND 12" GEOTEXTILE EXTENSION. ROLLS WILL BE CUSTOM LENGTHS AND CONTINUOUS THE ENTIRE SLOPE LENGTH.
- 4. EXTEND FLEXAMAT 10NW UV-T PAST THE CREST OF THE SLOPE AND INTO A 18" ANCHOR TRENCH. BACKFILL WITH COHESIVE SOILS.
- 5. INSTALL THE ADJACENT MAT OVER THE GEOGRID GEOTEXTILE EXTENSIONS.
- 5.1. ABUTMENT SEAMS SHALL BE SECURED IN 2' INCREMENTS USING STAINLESS STEEL ZIP TIES. ZIP TIES SHALL ENCOMPASS 3 CORDS OF GRID OF EACH MAT.
- 6. IF HEAD CUTTING IS ANTICIPATED EMBED THE TOE OF MAT INTO AN 18" ANCHOR TRENCH, BACKFILL WITH COHESIVE SOILS.
- 7. OPTIONAL: MAT MAY BE INFILLED WITH SOIL OR AGGREGATE.

## MOTZ ENTERPRISES, INC.

Flexamat 10oz-NW

(513)772-6689 Info@Flexamat.com Flexamat.com

